





**GENERAL NOTES**

1. ALL ACCESSORIES SHOWN HERE MAY NOT BE USED IN THIS PROJECT.
2. THESE ARE TYPICAL MOUNTING HEIGHTS FOR ACCESSORIES. SEE PLANS AND ELEVATIONS FOR SPECIFIC CONDITIONS AND ADDITIONAL INFORMATION.
3. MOUNT ALL ACCESSORIES PER MANUFACTURERS MOUNTING HEIGHT WHEN ACCESSIBILITY IS NOT REQUIRED.
4. SECURE ACCESSORIES TO WALL ONLY WHERE ADEQUATE IN-WALL BLOCKING EXISTS.
5. MOUNTING HEIGHT REQUIREMENTS FOR WASHROOM ACCESSORIES MAY VARY WITHIN A FACILITY DEPENDING ON THE LOCATION OF INDIVIDUAL ACCESSORIES AND THE DIRECTION OF REACH REQUIRED FOR THEIR USE.
6. TO ALLOW SIDE REACH BY PEOPLE IN WHEELCHAIRS, IT IS RECOMMENDED THAT ACCESSORIES BE MOUNTED WITH THEIR DISPENSING MECHANISMS, START BUTTONS, COIN SLOTS, OR DISPENSER OPENINGS LOCATED 38" TO 54" AFF, TO ENSURE FORWARD REACH ALSO. THEY MUST BE LOCATED NO MORE THAN 48" MAXIMUM FOR BOTH SIDE AND FORWARD REACHES. WHERE ELEMENTS ARE MOUNTED OVER OBSTRUCTIONS, SUCH AS COUNTERS, IT IS RECOMMENDED THAT THEY BE LOCATED NO MORE THAN 44" AFF. HOWEVER, DEPENDING ON THE DEPTH OF THE OBSTRUCTION, THESE CAN BE MOUNTED AS HIGH AS 48" FOR FORWARD APPROACH AND 54" FOR SIDE APPROACH.



GRAB BARS - BACK WALL

GRAB BARS - SIDE WALL


TA1  
DOUBLE-ROLL TOILET TISSUE DISPENSER

TA12  
MIRRORS

TA12a = DIMENSION  
TA12b = DIMENSION  
TA12c = DIMENSION

NOTE:  
SEAT HEIGHT SHALL BE BETWEEN 17"-19" AFF WALL OR FLOOR MOUNT. SEE PLUMBING.

NOTE:  
TOILET TISSUE DISPENSER SHALL BE INSTALLED BENEATH HORIZONTAL GRAB BAR 7"-9" BEYOND THE FRONT EDGE OF WATER CLOSET



SINK

TA7  
PAPER TOWEL DISPENSER

TA8  
ROLL PAPER TOWEL DISPENSER

TA10  
SOAP DISPENSER

TA15  
BABY CHANGING STATION

NOTE:  
EXPOSED PIPES SHALL BE INSULATED OR CONFIGURED TO PROTECT AGAINST CONTACT

MAXIMUM HEIGHT OF 48" ABOVE THE FLOOR TO HIGHEST OPERABLE PART OF THE DEVICE TO INSURE FORWARD REACH

40" ABOVE THE FLOOR SUGGESTED MOUNTING HEIGHTS FOR VARIOUS ACCESSORIES OPERABLE PART OF DEVICE

**1** **ACCESSORY MOUNTING DETAILS**  
SCALE: 1/2" = 1'-0"

**BID DOCUMENTS**  
**FREEMAN LAKE PARK OFFICE**  
ELIZABETHTOWN, KY 42701

ARCHITECTURAL	
PROJECT	2016-1340
DATE	8/18/2017
DRAWN	MSC
CHECKED	LEA
REVISIONS	
No.	Description

ICON ENGINEERING AND INSPECTION SERVICES, PLLC HAS RETAINED AN ELECTRONIC VERSION OF THESE DRAWINGS. THE CLIENT AGREES NOT TO REPRODUCE, REUSE, OR COPY THESE DRAWINGS IN ELECTRONIC OR ANY OTHER FORMAT OTHER THAN FOR THE SPECIFIC PROJECT LOCATION. THE CLIENT AGREES NOT TO TRANSFER THESE ELECTRONIC FILES TO OTHERS WITHOUT THE PRIOR WRITTEN CONSENT OF ICON ENGINEERING AND INSPECTION SERVICES, PLLC. THE CLIENT FURTHER AGREES TO WAIVE ALL CLAIMS AGAINST ICON ENGINEERING AND INSPECTION SERVICES, PLLC RESULTING IN ANY WAY FROM ANY UNAUTHORIZED CHANGES TO OR REUSE OF THE ELECTRONIC FILES FOR ANY OTHER PROJECT BY ANYONE OTHER THAN ICON ENGINEERING AND INSPECTION SERVICES, PLLC.

**ACCESSORY DETAILS**

**A-503**

© 2017 ICON ENGINEERING